

Application / Advice / Consent for Connection to Wannon Water Main

PROPERTY DETAILS

Insufficient information will result in the return of applications. If you cannot provide all the property details, a locality plan showing dimensions of property frontage and distance from nearest street intersection must be attached to this application

Street No _____ Street : _____ Town: _____ PC: _____
 Lot No: _____ Subdivision Plan No: _____ Crown Allotment: _____ Section: _____

PROPOSED WORK (Note: Initial Site Plan required to be lodged with this form) Please tick () all applicable boxes

Property Type

- Residential (single) Residential (multi-unit)
 Commercial / Industrial* (Please note: that an "As-Constructed plan" will be required)

*Type of Business(eg hairdresser, milk bar, motel etc) _____

Type of Work

- New connection to Water Main Disconnection from Water Main
 Fire Service ("As-constructed" Plan Required) Water by Agreement
 Backflow Prevention Device Meter Only
 Service Size, Type Required & Anticipated Water Usage Other (connect water tank to house plumbing)

Domestic / Residential _____ mm Type (eg copper) _____
 Fire Service _____ mm Type (eg copper) _____ Water Usage greater than 10ML Yes No
 Please note that an initial site plan and a "As Constructed Plan" is required for fire services showing back flow prevention and fittings

PROPERTY OWNER DETAILS

Name: _____
 Postal Address: _____ PC: _____
 Ph: _____ Mb: _____ Fax: _____ Email: _____

I hereby make application to Wannon Water for consent to connect/ alter water plumbing at the property described above, in accordance with Wannon Water requirements and conditions of connection (page 2)

Signature of owner (or agent) _____ Date of Application _____

PLUMBER DETAILS

Name: _____ Licence No: _____
 Business Name: _____ Ph: _____
 Postal: _____ Fax: _____
 Email: _____

Office Use only

CHARGES/FEES PAYABLE BY THE OWNER PRIOR TO CONNECTION

	Amount \$	Date Paid	Receipt No	Account?
Tapping Fee:	\$ _____	____/____/____	_____	<input type="checkbox"/>
Meter Fee:	\$ _____	____/____/____	_____	<input type="checkbox"/>
Disconnection Fee:	\$ _____	____/____/____	_____	<input type="checkbox"/>
New Customer Contribution	\$ _____	____/____/____	_____	<input type="checkbox"/>
Other _____	\$ _____	____/____/____	_____	<input type="checkbox"/>
Total \$	_____			

Notes:

AQUARATE PROPERTY ACCOUNT No:

CONSENT On signing by a Wannon Water Authorised Officer, consent is given to the Owner for the undertaking of the work described above – subject to the Conditions of Connection (page 2) **NOTE: This Consent expires 12 months after Consent Date**

Tapping Size: _____ mm	Meter No: M _____
Meter Size: _____ mm	RF Unit ID: _____
Main Size: _____ mm Main Type: _____	Meter Reading: _____ KL
Tapping Date : _____ Time: _____	Installation Date: ____/____/____
Name: (of Authorised Officer) _____	Issued By: _____
Date of Consent: ____/____/____	Location: _____
Signature (of Authorised Officer) _____	Distance from nearest Boundary: _____
	Btw Meter Nos: _____ & _____

05/13

Completed forms can be emailed to info@wannonwater.com.au

wannonWATER


www.wannonwater.com.au

PO Box 1158
 Warrnambool VIC 3280
 Ph: 1300 926 666 Fax: 03 5565 6050

CONDITIONS of CONNECTION to Wannon Water WATER Main

1. A complete proposed plan (see Item 9) must accompany the application. All fees and charges applicable to the work shall be paid prior to application processing. Wannon Water will not connect the service until all fees are paid.
2. The Owner, or Owner's Agent (Plumber), must give Wannon Water a minimum of five (5) working days of intention to connect for new or altered works.
3. The service pipe from the tapping to meter shall be 90° to the property building line unless prior approval from Wannon Water has been obtained.
4. The service pipe and meter arrangement shall be in accordance with AS 3500 and Wannon Water's standard arrangement which only permits the following:
 - a) B Grade Copper, OR
 - b) Class 12.5 or 16 Poly Ethylene (PE) 100.
5. Water pumps are only to be connected with specific approval from Wannon Water.
6. The materials used, and the installation of the works on site, shall be in accordance with Plumbing Regulations, all relevant Australian Standards and the Water Act.
7. A Preliminary Site Plan showing locations of Domestic / Industrial / Commercial Water Services and/or Fire Services, Backflow Prevention Devices/ Testing Ferrules must be submitted with the Application. As Constructed Plans are to be forwarded to Wannon Water within 10 working days of connection to the Wannon Water main.
8. A Water Main Location shall be obtained from Wannon Water prior to the completion & submission of this form / plan. Please allow twenty-four (24) hours' notice to Wannon Water for the provision of this Water Main Location information.
9. Applications will ONLY be approved if the following details are shown on the Proposed Plan:
 - a) Plan of block showing all title boundaries and subdivisions (inc proposed or existing building/units) with Lot and/or Street number
 - b) Type and size of existing water main
 - c) Proposed or existing driveway/s and proposed or existing crossroad conduit/s
 - d) Proposed location of meter (with distance from nearest side boundary)
 - e) A detailed drawing of the proposed service pipe (including type and size)
 - f) Tapping location
 - g) North Point and road/s with road name/s
 - h) Any sluice valves/testable backflow device / hydrant / hose reels / sprinkler system (if applicable)
10. Annual usage great than 10ML requires waterMap registration and preparation by owner.
11. A minimum of three days must be allowed when booking tappings, cut-ins, etc.
12. The tapping hole size is to meet the dimensions stipulated in the metering manual. Excavation for water tappings are to be a minimum of 1200mm x 1200mm with 300mm clearance under the pipe and in accordance with OHS standards.
13. Use bedding sand for reinstatement of bedding material to 150mm above the ferrule bend in excavated tapping holes.
14. Tappings will only be completed if a licensed plumber is on site. If no plumber is present, a new time will be booked & a recharge fee will apply.

Example of detail required for plan to accompany domestic water service connection application:



PROPOSED PLAN FOR WATER SERVICE CONNECTION


See conditions of connection to Wannon Water water main

Street No _____ Street : _____ Town: _____ Postcode: _____
Lot No: _____ Subdivision Plan No: _____ Crown Allotment: _____ Section: _____

Declaration

I/We _____ (Company/Plumber) on this date ____/____/20____ sign to declare that the water meter has been or will be installed correctly.

Name: _____ Signature: _____

<p>I, _____ (Name of Authorising officer)</p> <p>on ____/____/____ (Date)</p> <p>confirm the measurements provided on this plan are accurate and therefore is authorised as an "AS CONSTRUCTED"</p>	
---	--

Completed forms can be emailed to info@wannonwater.com.au



wannonWATER

PO Box 1158
Warrnambool VIC 3280
Ph: 1300 926 666 Fax: 03 5565 6050
www.wannonwater.com.au